

**The Philadelphia Parking Authority  
Mellon Independence Center  
701 Market Street, Suite 5400  
Philadelphia, PA 19106**

**Bid No. 17-14  
Proposed Parking Lots at  
Ben Franklin Bridge and Third Street  
Addendum Three**

To: See Email Distribution List  
From: Mary Wheeler  
Manager of Contract Administration  
Date: August 17, 2017  
No Pages: 1

This addendum is issued on August 17, 2017 prior to the bid due date to add, delete, modify, clarify and/or to respond to questions submitted by prospective bidders regarding the work included in the above referenced solicitation.

**CLARIFICATIONS, CHANGES AND ADDITIONS TO THE BID DOCUMENTS**

Subsurface conditions: In some instances where the owner, the DRPA, has previously performed excavations under the existing setts, they found a concrete slab approximately one foot thick with steel wire welded fabric near the bottom of the slab. The setts were not bedded in the concrete. It is not known if this condition is consistent throughout under all the setts.

Bidders should assume this subsurface condition exists, and include the costs to saw cut and remove the existing slab in their bid. This would occur only where a trench is cut for conduit (approx. 62 LF), or where a fence post is augured, but not for the entire area of the proposed concrete lanes and islands, which would go on top of any existing slab. Refer to revised drawing CD1.0 for new detail 4/CD1.0.

**END OF ADDENDUM THREE**